

SPECIFICATION TEMPLATE FOR:

FLOOR MATS & FRAMES – Nuway

RESILIENT FINISHES

PART 1 – GENERAL

1.1 Scope

Supply and Installation of recessed Floor Mats including related accessories and equipment to all areas nominated below and/or on plans.

Including but not limited to:

- a) Frames / T-Bars
- b) Screeding
- c) (NUGRID under matting drainage system)
- d) Cutting to shape

1.2 Related Work

Coordinate and cooperate with the following trades:

- Granolithic Work [check for allowance for frames depth to suit Matting]
- Door Work
- Paving / Tiling Work
- Carpet / Vinyl Work
- Hydraulic (in case of drainage)

1.3 Quality Assurance

Installers are required to be extensively experienced in the relevant aspects and class of work required for this section. Installers must follow Novaproducts Global instructions for installation.

1.4 References

N/A

1.5 Submissions

Provide data sheets of all materials, including cleaning and maintenance, warranty and product summary.



1.6 Delivery, Handling & Storage

All materials to be stored in a dry secure area away from any hazardous goods.

Order in sufficient time prior to scheduled requirement; to avoid delays.

Pre-sized Nuframe must not be size adjusted without approval from Novaproducts Global

1.7 Warranty

Installer shall provide a warranty covering all aspects of the installation performed by this trade, against defective materials for a period of 15 years from the date of installation.



PART 2 – MATERIALS

2.1 Materials

Mats:

Nuway Tuftiguard (Design / Classic / Plain) reversible, double sided set in standard Nuframe, all to manufacturers current written instructions. Thickness to be (12mm / 17mm). (Closed / Semi-open) Construction.

(Module One – 15mm scraper bar, 15mm wiper strip or/ Module Two – 15mm scraper bar, 30mm wiper strip)

Frames:

25 x 18mm reversible Nuframe to be manufactured by Novaproducts Global.

2.1.1 Proprietary item: Matting shall be NUWAY Tuftiguard matting - Available from NOVAPLAS ARCHITECTURAL PRODUCTS Pty Ltd (Tel: 618 9455 2228)

2.1.2 Wiper Strip colour: (Black / Natural Grey) (Other – please specify _____)
[Classic is only natural Grey / all colours are design.]

Aluminium scraper bars: Mill Finish (Anodised – special option)

2.1.3 Location/ Zones: Refer Architectural Drawing No. _____
Refer to Schedule of finishes pages _____

Door No _____ [repeat for each door] [use in BOQ]

Size of mat/s shall be ___mm (L-R) x ___mm (F-B) walking direction

2.2 Schedule of Quantities

(Refer to drawings for locations and colours of items)

(Refer to bill of quantities of colours and items)



PART 3 – EXECUTION

3.1 Examination

Inspect the site conditions related to each installation. Arrange for correction if required. Commencement of installation work on site means total acceptance of conditions. Check site measurements prior to final manufacture of sizes.

3.2 Installation

[If drainage is required], (plumber should install stormwater pipe to matwell. Do not create falls.)

Granolithic work should prepare and allow for matwells in pour.

Provide mat recess in floor to accept the size of mat required.

Refer to drawings for location of the mats.

For site assembly and installation by contractor of abutting flooring / finish

Must be fixed to masonry concrete to suit floor finish height, then screeded with a recognised hard screed to a depth of (17mm / 12mm) from the top of the frame to suit mats. Frames must be kept level and square.

3.3 Preparation

Comply with reference standards and manufacturer's recommendations.

Mats not to be installed until location is enclosed and weatherproof, and not until work space is completed and dry.

3.4 Cleaning & Protection

Preinstall then either protect with carpet remnants or store mats until project is near completion.



On completion of mat recess or area; remove all dirt, scraps and left over materials and clean the area. Remove and replace work which cannot be successfully cleaned or repaired.

3.5 Completion

Complete all contracted work in accordance with contract documents and written variation orders issued by the Architect.

Work will be regarded complete after being inspected and approved.

Specifiers Note: Brackets () show options to choose from.

Brackets [] show notes.

END OF SECTION

